

DEVON WASTE WATER TREATMENT PLANT

No.	Description	Unit	Qty	Rate	Amount
	All work to be done according to the National building regulations,				
1	Preliminary and general	Sum	1	R	R
2	Remove existing single doors	no	8	R	R
3	Remove existing double door	no	1	R	R
4	Remove existing vinyl tiles and prepare surface for new tiling	m ²	51,15	R	R
5	Supply and fit ceramic tiles including grouting	m ²	51,15	R	R
6	Supply and install 2032 x 813mm hollow core doors complete with 2 lever motice locks sets and striker plates	no	6	R	R
7	Supply and install 2032 x 813mm finger joint doors complete with 3 lever motice locks sets and striker plates	no	2	R	R
8	Supply and install double door finger joint doors with complete lockset	no	1	R	R
9	Apply 2 coat enamel paint to hollow core doors	no	6	R	R
10	Apply 2 coat varnish to external doors	m ²	28,8	R	R
11	Paint door frame	no	9	R	R
12	Paint window seal	no	5	R	R
11	Supply and Fit Kitchen Cupboard with Granite Top.	Item	1	R	R
12	Remove existing lights, supply and fit flourescent light	no	6	R	R
13	Supply and Fit 200L electric geysers	Item	1	R	R
	Supply new electrical points	no	2	R	R
14	Service to Plumbing works	Item	1	R	R
15	Prepare and paint ceiling slab with 2 coats	m ²	51,15	R	R
16	Prepare and paint walls with 2 coats	m ²	153,94	R	R
17	Contingencies	%	5	R	R
				SUB TOTAL	R
				TOTAL	R

Note: All quantities are subject to re-measure

BIDDER:

SIGNATURE:

DATE: